



PROFESSIONAL ESTIMATION  
SUITE  
Material planning built for the  
field.

MATERIAL ESTIMATE  
**Miller Household**  
September 3, 2026

|                                              |                                           |                                  |
|----------------------------------------------|-------------------------------------------|----------------------------------|
| JOB NAME<br><b>Miller Household</b>          | JOB ADDRESS<br><b>14725 31st Ave N</b>    | CONTRACTOR<br>—                  |
| ESTIMATOR<br>—                               | ESTIMATE DATE<br><b>September 3, 2026</b> | REPORT ID<br><b>DTB-20260903</b> |
| PROJECT NOTES<br>the project looks very well |                                           |                                  |

PURCHASE PLANNING

Material Takeoff

Recommended purchase quantities generated from the current calculator inputs.

|                                          |                                                |                                    |                                        |                                        |
|------------------------------------------|------------------------------------------------|------------------------------------|----------------------------------------|----------------------------------------|
| DRYWALL SHEETS 01<br><b>27</b><br>sheets | JOINT COMPOUND 02<br><b>2</b><br>5-gal buckets | JOINT TAPE 03<br><b>1</b><br>rolls | CORNER BEAD 04<br><b>4</b><br>sections | DRYWALL SCREWS 05<br><b>2</b><br>boxes |
|------------------------------------------|------------------------------------------------|------------------------------------|----------------------------------------|----------------------------------------|

CALCULATION RECORD

Estimate Details

Inputs, assumptions, and calculated quantities organized by calculator.

| 01 · BOARD TAKEOFF<br><b>Drywall Sheets</b> |            | RECOMMENDED QUANTITY<br><b>27</b> SHEETS |           |
|---------------------------------------------|------------|------------------------------------------|-----------|
| PROJECT INPUTS                              |            | CALCULATED TAKEOFF                       |           |
| Sheet size                                  | 4×12 ft    | Wall area                                | 684 sq ft |
| Hang direction                              | Horizontal | Ceiling area                             | 0 sq ft   |
| Wall count                                  | 4          | Opening deductions                       | 72 sq ft  |
| Ceiling height                              | 9 ft       | Net board area                           | 612 sq ft |
| Ceiling included                            | No         | Base sheets                              | 24        |
| Applied waste factor                        | 10%        | Layout waste indicator                   | 16%       |
|                                             |            | Total joint footage                      | 188 lf    |

02 · FINISHING MATERIAL

Joint Compound

5-GALLON BUCKETS

2 BUCKETS

FINISH SPECIFICATION

|                 |                   |
|-----------------|-------------------|
| Calculated area | 612 sq ft         |
| Finish level    | Level 2           |
| Compound type   | Setting (Hot Mud) |
| Coat count      | 2                 |

MATERIAL REQUIREMENT

|                     |                            |
|---------------------|----------------------------|
| Total compound      | 6.12 gal                   |
| 1-gallon equivalent | 7 buckets                  |
| Calculation source  | Synced from sheet net area |

03 · JOINT TREATMENT

Joint Tape

RECOMMENDED QUANTITY

1 ROLLS

TAPE SPECIFICATION

|                    |                              |
|--------------------|------------------------------|
| Tape type          | Paper tape                   |
| Roll size          | 250 ft                       |
| Calculation source | Layout-derived joint footage |

COVERAGE REQUIREMENT

|                |        |
|----------------|--------|
| Joint footage  | 188 ft |
| Corner footage | 36 ft  |
| Total tape     | 235 ft |

04 · OUTSIDE CORNERS

Corner Bead

RECOMMENDED QUANTITY

4 SECTIONS

BEAD SPECIFICATION

|              |                   |
|--------------|-------------------|
| Bead type    | Metal corner bead |
| Stock length | 10 ft             |

LINEAR REQUIREMENT

|                      |       |
|----------------------|-------|
| Straight corners     | 36 ft |
| Arch / flexible bead | 0 ft  |
| Total bead           | 36 ft |

05 · FASTENERS

Drywall Screws

RECOMMENDED QUANTITY

2 BOXES

FASTENER SPECIFICATION

|              |            |
|--------------|------------|
| Screw length | 1-5/8"     |
| Application  | Walls      |
| Sheets used  | 27         |
| Box size     | 875 screws |

CALCULATED QUANTITY

|                    |                            |
|--------------------|----------------------------|
| Screws per sheet   | 45                         |
| Total screws       | 1,337                      |
| Calculation source | Synced from sheet quantity |

Material quantities are planning estimates based on the dimensions, selections, and waste factors entered in the Drywall Toolbox calculators. Verify field measurements, project specifications, manufacturer requirements, and applicable local code before purchasing or installing materials.